

Subdivisional Lines, T 4 N R 39 E W M.

Chains

T 4 N S 7 on N.E.
 R 39 E S 18 on S.E.
 R 38 E S 13 on S.W. and
 S 12 on N.W. faces, with
 2 notches on N. and
 4 notches on S. edges;

from which

A spruce, 10 ins. diam., brs. N.41°E., 29 lks. dist.,
 marked T 4 N R 39 E S 7 B T.

A spruce, 13 ins. diam., brs. S.44°E., 51 lks. dist.,
 marked T 4 N R 39 E S 18 B T.

A spruce, 15 ins. diam., brs. S.48°W., 34 lks. dist.,
 marked T 4 N R 38 E S 13 B T.

A spruce, 12 ins. diam., brs. N.42°W., 50 lks. dist.,
 marked T 4 N R 38 E S 12 B T.

Thence I run

S.89°42'E., on true line bet. Secs. 7 & 18, with same Var.
 Gently ascending.

40.26 Top of high raise, course N. & S.

Descend along hillside, facing S.E.

78.26 Set fir post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for

$\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on N. face; from which

A fir, 13 ins. diam., brs. N.11°W., 32 lks. dist.,
 marked $\frac{1}{4}$ S B T.

A fir, 18 ins. diam., brs. S.8°W., 20 lks. dist.,
 marked $\frac{1}{4}$ S B T.

Descending gently to

118.26 The Cor. to Secs. 7, 8, 17 & 18.

Land; rolling.

Soil; 2nd rate.

Densely covered with forests of pine, spruce & tamarack,

118.26 chs.

Thick undergrowth of huckleberry & spruce, 118.26 chs.

May 7, 1884.