

Subdivisional Lines of T. 4 S., R. 30 E., W.M.

| Chains | | Feet |
|--------|---|------|
| 40.00 | Set a basalt stone 18 x 10 x 10 ins. in mound of stone, in open glade, on N. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face. No trees near. | |
| 56.00 | A spring branch, course N.E. | |
| 80.00 | <p>Set a basalt stone 14 x 8 x 7 ins. 10 ins. in ground on level in Prairie, N. of and near open timber for Cor. to Secs. 8, 9, 16 and 17, marked with 4 notches on S. and E. edges.</p> <p>A Pine 20 ins. diam. brs. S. 26° W. 140 lks. dist. marked T. 4 S., R. 30 E., S. 17 B.T.</p> <p>No other trees near, raised mound of stone alongside in lieu of pits. (descent about 200 ft)</p> <p>Land; surface rolling,</p> <p>Soil; 3rd and 2nd rate, scattering Pine timber with large open glades.</p> | |
| | <p>E. on a random line bet. Secs. 9 and 16,</p> <p style="text-align: right;">Var. 21° 00' E.</p> | |
| | Nearly level, | |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. | |
| 53.00 | C. M. Radcliff's house brs. S. about 6 chs. | |
| 74.00 | <p>A brook 10 lks. wide, course N.W.</p> <p>Descent about 100 ft.</p> | |
| 80.28 | <p>Intersected N. and S. line 4 lks. N. of Cor. to Secs. 9, 10, 15 and 16. Thence I run,</p> <p>N. 89° 58' W. on a true line bet. Secs. 9, and 16.</p> <p style="text-align: right;">Var. 21° 00' E.</p> | |
| 40.14 | <p>Set a basalt stone 12 x 10 x 8 ins. 8 ins. in ground on slight S. slope for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, no trees, raised a mound of stone alongside in lieu of pits.</p> | |
| 80.28 | <p>The Cor. to Secs. 8, 9, 16 and 17.</p> <p>Land; surface W $\frac{1}{2}$ mile undulating, E. $\frac{1}{2}$ mile rolling,</p> <p>Soil; 1st, 2nd and 3rd rate. Some Pine timber along brook, remainder prairie. Good grass.</p> | |