

Exterior Lines of T. 5 S., R. 31 E. W.M.

Chains		Feet
	N. 89° 54' E. on a true line along the N. Bdy. of Sec. 4. Var. 20° 00' E	
40.00	A Pine 20 ins. diam. on N. slope for $\frac{1}{4}$ Sec. Cor. A Pine 24 ins. diam. brs. N. 58° W. 88 lks. dist. " " 16 " " " S. 14° E. 122 " "	
80.00	Set basalt stone 16 x 8 x 7 and post in mound of stone on level for Cor. to Secs. 3, 4, 33 and 34. Land; surface rolling on W. 60 Chs., E. 20 Chs. level; Soil; 2nd and 3rd and 1st rate. Occasionally groves of Pine timber. Good grass. Some excellent farming land.	
	N. 89° 54' E. on a true line along the N. Bdy. of Sec. 3. Var. 20° 45' E.	
33.50	A cabine, 250 lks. N. of line	
40.00	Drove a marked Tamarack stake in soft soil for $\frac{1}{4}$ Sec. Cor. This is more permanent here than post in mound.	
80.00	Set post, dug pits and raised mound of earth for Cor. to to Secs. 2, 3, 34 and 35. Land; surface nearly level, Soil; first rate. Good grass, excellent farming land.	
	N. 89° 54' E. on a true line along the N. Bdy of Sec. 2 Var. 19° 30' E	
3.50	Spring branch, course S.E.	
19.50	Snipe creek, 20 lks. wide, course S.W.	
40.00	Set Willow post in mound of stone on level for $\frac{1}{4}$ Sec. Cor.	
80.00	Set Tamarack Post and stone, basalt 16 x 7 x 6, dug pits and raised mound of earth on level for Cor. to Secs. 1, 2, 35 and 36. Land surface nearly level, Soil; 1st rate, excellent grass. Good natural meadows, excellent farming land.	