

Exterior Lines of T. 4 S., R. 31 E., W.M.

Chains		Feet
	N. on the E. Bdy. of Sec. 36,	
		Var. 19° 30' E.
9.00	Enter timber, course E. and W.	
40.00	Set Pine post on slight N. slope for $\frac{1}{4}$ Sec. Cor.	
	A Pine 40 ins. diam. brs. S. 44° E. 104 lks. dist.	
	" " 20 " " " N. 37° W. 34 " "	
53.00	Owens Creek 12 lks. wide, course S.W.	
80.00	Set Pine post on level for Cor. to Secs. 25, 36, 30 & 31.	
	A Pine 4 ins. diam. brs. N. 60° E. 30 lks. dist.	
	" " 10 " " " S. 77° E. 146 " "	
	" " 10 " " " S. 80° W. 104 " "	
	No trees N.W.	
	Land; surface undulating,	
	Soil; 1st and 2nd rate. Some Pine timber, but not heavy.	
	Good grass. Excellent farming land.	
	<hr/>	
	N. on the E. Bdy. of Sec. 25,	
		Var. 20° 00' E.
40.00	Set basalt stone 18 x 10 x 5 on slight S. slope for $\frac{1}{4}$ Sec. Cor.	
	A Pine 12 ins. diam. brs. N. 86° E. 34 lks. dist.	
	A Pine 6 ins. diam. brs. S. 68° W. 54 lks. dist.	
71.00	Leave timber, course E. and W.	
80.00	Set Pine post, dug pits and raised mound of earth for Cor. to Secs. 24, 25, 19 and 30. No trees.	
	Land; surface undulating,	
	Soil; 1st rate. Some scattering thick groves of Pine timber. Good grass. Good farming land.	
	<hr/>	
	N. on the E. Bdy. of Sec. 24,	
		Var. 19° 45' E.
28.00	Fence and Field, course E. and W.	
39.00	" " leave field, course E. and W.	
40.00	Set basalt stone 14 x 12 x 10 on level for $\frac{1}{4}$ Sec. Cor.	
	A Pine 11 ins. diam. brs. N. 11° E., 184 lks. dist.	