

## Subdivisional Lines of T. 4 S., R. 31, E. W.M.

Chains		Feet
14.00	A ravine, course from N. to S.	-100
15.00	Wagon road, course N. and S.	
26.00	On spur, extends S.	+ 80
40.25	Set basalt stone 16 x 10 x 7 on S.W. slope for $\frac{1}{4}$ Sec. Cor. in mound of stone. Peck's house brs. S. 28° W.	
55.00	" " " S. 31° E.	
80.50	The Cor. to Secs. 11, 12, 13 and 14. Land; surface rolling, Soil; 3rd and 2nd rate, scattering Pine, Tamarack and Fir timber.	
	N. bet. Secs. 11 and 12, Var. 22° E.	
3.00	Begin ascent of mountains proper,	
40.00	Set basalt 16 x 8 x 7 on flat for $\frac{1}{4}$ Sec. Cor. A Pine 12 ins. diam. brs. S. 43° E. 111 lks. dist. " " 10 " " " N. 76° W. 180 " "	
63.50	A spring branch, course S.W.	
80.00	Set basalt stone 17 x 12 x 8 in small open flat in mound of stone for Cor. to Secs. 1, 2, 11 and 12. A Pine 10 ins. diam. brs. N. 38° E. 125 lks. dist. A Pine 22 ins. diam Brs. S. 77° E. 115 lks. dist. A Pine 34 ins. diam. brs. N. 21° W. 164 lks. dist. No trees S.W. Land; surface mountainous. Soil; 3rd and 2nd rate, Pine, Tamarack and Fir timber with open glades, good bunch grass. A small part of the land can be farmed.	+300
	E. on a random line bet. Secs. 1 and 12. Var. 21° 00' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.26	Intersected E. Bdy 2 lks. N. of Cor. to Secs. 1 and 12, from which Cor. I run,	