

## Subdivisional Lines of T. 4 S., R. 31 E., W.M.

Chains		Feet
	Pine, Tamarack and Fir timber. Good grass. Some good farming land.	
	Oct. 27, 1880	
	E. on a random line bet. Secs. 4 and 9.	
	Var. 20°30'E	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.16	Intersected N. and S. line 12 lks. N. of Cor. to Secs. 3, 4, 9 and 10, from which Cor. I run, N. 89° 55' W. on a true line bet. Sec. 4 and 9.	
	Var. 19° 45' E.	
18.50	Fence, & leave field, course N.E. and S.W.	
40.08	Set basalt stone 18 x 10 x 8 in mound of stone on E. slope for $\frac{1}{4}$ Sec. Cor.	
	A Pine 40 ins. diam. brs. N. 42° E. 240 lks. dist.	
	No other trees.	
80.16	The cor. to Sec. 4, 5, 8 and 9 Land; surface undulating, Soil; 1st, 2nd and 3rd rate. Some scattering Pine timber, good bunch grass, about $\frac{1}{2}$ of Sec. 9 is good farming land.	+100
	N. on a random line bet. Sec. 4 and 5.	
	Var. 20°30'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
65.85	Intersected N. Bdy., 72 lks. W. of Cor. to Secs. 4 and 5, from which Cor. I run, S. 00°31' W. on a true line bet. Secs. 4 and 5,	
28.85	Set basalt stone 18 x 8 x 7 on S.E. slope for $\frac{1}{4}$ Sec. Cor. in mound of stone.	
32.50	Wagon road, course N.W. and S.E.	
65.85	The Cor. to Secs. 4, 5, 8 and 9 Land; surface rolling and broken, Soil; 3rd and 2nd rate, Pine, Tamarack and Fir timber with large open glades. About $\frac{1}{2}$ of Sec. 4 is good farm-	-150