

## Subdivisional Lines, T.4 S., R.32 E., W. M.

|  |  |
|--|--|
| Chains   | N.89°54'W. on true line bet. Secs. 12 & 13.<br>Var.18°00'E.  |
| 13.50  | A brook, 6 lks. wide, course S.E.  |
| 28.00  | A large open glade.  |
| 39.79  | Set basalt stone, 15 x 10 x 4 on level, in open glade, for<br>¼ Sec. Cor. No trees near.   |
| 47.00  | Enter timber, course S.E. & N.W.   |
| 79.58  | The Cor. to Secs. 11, 12, 13 & 14.<br>Land; surface E. ½ mile, very broken, W. ½ mile, rolling.<br>Soil; 3rd & 2nd rate.<br>Heavy pine, tamarack & fir timber, with open glades.<br>June 16, 1881.   |
| N. bet. Secs. 11 & 12.<br>Var.19°00'E.               |  |
| 40.00  | Set basalt stone, 18 x 12 x 4, on slight N.E. slope, for<br>¼ Sec. Cor.<br>A fir, 20 ins. diam., brs. N.20°E., 48 lks. dist.<br>A pine, 11 ins. diam., brs. S.54°W., 101 lks. dist.  |
| 73.50  | Spring branch, course E.   |
| 80.00  | Set basalt stone, 16 x 10 x 4, in open glade on S.W. slope<br>for Cor. to Secs. 1, 2, 11 & 12.<br>A pine, 13 ins. diam., brs. N.67°E., 122 lks. dist.<br>A " 40 " " " S.81°E., 204 " "<br>A " 15 " " " S.28°W., 225 " "<br>No tree N.W.<br>Land; surface rolling.<br>Soil; 2nd rate.<br>Heavy pine, tamarack & fir timber, with open glades.<br>Some underbrush. |
| E. on random line bet. Secs. 1 & 12.<br>Var.18°15'E. |  |
| 40.00  | Set post for temp. ¼ Sec. Cor.   |
| 80.40  | Intersected E. Bdy., 68 lks. N. of Cor. to Secs. 1 & 12, from<br>from which Cor., I run<br>N.89°31' W. on true line bet. Secs. 1 & 12.   |