

Exterior Lines, T.5 S.,R.34 E.,W. M.  
 As surveyed by Rufus S. Moore,  
 Under Contract No. 451,  
 Dated June 12, 1882.

Chains

From the Cor. to Tps. 4 & 5 S.,Rs. 33 $\frac{1}{2}$  & 34 E.,

I run

E. on random line on N. Bdys. of Secs. 6, 5, 4, 3, 2, & 1

Var.18°15'E.

Set temp.  $\frac{1}{4}$  Sec. & Sec. Cors. at every 40 & 80 chs. and at  
 6 miles, 1 ch. and 20 lks.

Intersect E. Bdy. of Tp. at Cor. to Tps. 4 & 5 S.,Rs. 34 &

35 E., which is a post, 4 ins. sq., marked

T.4 S.,R.35 E.,S.31 on N.E.

R.35 E.,S.6 on S.E.

T.5 S.,R.34 E.,S.1 on S.W. and

S.36 on N.W. faces,with

6 notches on each edge, from which

A pine, 14 ins. diam.,brs. S.39°W., 33 lks. dist.,  
 marked T.5 S.,R.34 E.,S.1,B.T.

A pine, 26 ins. diam.,brs. N.53°W., 84 lks. dist.,  
 marked T.4 S.,R.34 E.,S.36,B.T.

A pine, 16 ins. diam.,brs. N.47°E., 51 lks. dist.,  
 marked T.4 S.,R.35 E.,S.3k,B.T.

A pine, 30 ins. diam.,brs. S.43°E., 70 lks. dist.,  
 marked T.5 S.,R.35 E.,S.6,B.T.

Thence I run

W. on N. Bdy. of Sec. 1.

\*\*\*\*\*

W. on N. Bdy. of Sec. 3.

\*\*\*\*\*

80.00 Set post, 4 $\frac{1}{2}$  ft. long, 4 ins.sq., 24 ins. in ground, for Cor.

to Secs. 3, 4, 33 & 34, marked

T.4 S.,R.34 E.,S.34 on N.E.

T.4 S.,R.34 E.,S.33, on N.W.

R.34 E.,T.5 S.,S.4 on S.W. and

T.5 S.,R.34 E., S.3 on S.E., with

3 notches on E. & W. edges, from which

A pine, 16 ins. diam.,brs. N. 8°E., 62 lks. dist.,  
 marked T.4 S.,R.34 E.,S.34,B.T.