

Exterior Bdys. T 5 N., R. 28 E., W.M.  
 As surveyed by Timothy W. Davenport, U.S. Dept. Surveyor,  
 Under Contract No. 101,  
 Dated Aug. 5, 1861.

Chains	Monday, Sept. 9, 1861.
	<p>Beginning at the post, the established Cor. to Tps. 5 N.,            Rs. 28 &amp; 29 E., on the 1st Standard Parallel N.            Thence            N. bet. Secs. 31 &amp; 36.</p> <p style="text-align: right;">Var. 21° E.</p>
40.00	Set $\frac{1}{4}$ Sec. Cor.; made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 30, 31, 25 & 36; made mound and deposited charred stake as per instructions.
	<p>Surface; undulating.            Soil; sandy, with heavy sage and greasewood. In vacant places, bunch grass.</p>
	<p>N. bet. Secs. 25 &amp; 30.</p> <p style="text-align: right;">Var. 20° 30' E.</p>
40.00	Set post for $\frac{1}{4}$ Sec. Cor.
	Made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 19, 30, 24 & 25; made mound and deposited charred stake as per instructions.
	<p>N. bet. Secs. 19 &amp; 24.</p> <p style="text-align: right;">Var. 20° 30' E.</p>
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
58.00	Main Columbia Trail, course E. & W.
80.00	Set post Cor. to Secs. 13, 18, 19 & 24; made mound and deposited charred stake, as per instructions.
	<p>This mile has less sage and greasewood than the previous ones.            Surface; some rocky.</p>
	<p>N. bet. Secs. 13 &amp; 18.</p> <p style="text-align: right;">Var. 20° 30' E.</p>
40.00	Set $\frac{1}{4}$ Sec. post; made mound and deposited charred stake, as per instructions.