

Subdivisional Lines, T 5 N R 28 E W M.

Chains	
80.80	To Cor. of Secs. 22, 23, 26 & 27.
<hr/>	
N. bet. Secs. 22 & 23.	
Var. 20°45'E.	
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 14, 15, 22 & 23; made mound and drove charred stake, as per instructions.
<hr/>	
E. on random bet. Secs. 14 & 23.	
Var. 20°45'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.65	Intersect N. & S. line, 30 lks. N. of Cor. to Secs. 13, 14, 23 & 24.
N. 89°47'W. on true line bet. Secs. 14 & 23.	
40.32 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. Cor. post, in mound, with charred stake, as per instructions.
60.65	Columbia Trail, course S. 50°E.
80.65	To Cor. of Secs. 14, 15, 22 & 23.
<hr/>	
N. bet. Secs. 14 & 15.	
Var. 20°45'E.	
11.00	Columbia Trail, course E. & W.
40.00	Set $\frac{1}{4}$ Sec. post, in mound, with charred stake, as per instructions.
80.00	Set post Cor. to Secs. 14, 15, 10 & 11; made mound and drove charred stake, as per instructions.
<hr/>	
E. on random bet. Secs. 11 & 14.	
Var. 20°30'E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.75	Intersect N. & S. line, 30 lks. N. of Cor. to Secs. 11, 12, 13 & 14.
N. 89°47'W. on true line bet. Secs. 11 & 14.	