

## Subdivisional Lines, T 5 N R 28 E W M.

Chains	Friday, Sept. 13, 1861.
N. bet. Secs. 32 & 33.	Var. 21° E.
15.70 Trail leading E. & W.	
40.00 Set $\frac{1}{4}$ Sec. post; made mound; drove charred stake, as per instructions.	
80.00 Set post Cor. to Secs. 28, 29, 32 & 33; made mound and drove charred stake, as per instructions. Surface; undulating. Soil; sandy, with sage, etc.	
E. on random line bet. Secs. 28 & 33.	Var. 21° 6' E.
40.00 Set temp. $\frac{1}{4}$ Sec. post.	
80.10 Intersect N. & S. line, 10 lks. S. of Sec. Cor. S. 89° 56' W. on true line bet. Secs. 28 & 33.	
.50 Top of rock.	
40.05 Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.	
49.00 Umatilla landing road, course N.	
61.00 Umatilla River, 1.25 chs. broad, runs N. Water in channels, * in rock.	
63.10 To W. bank.	
65.00 Top of bank.	
80.10 To Cor. of Secs. 28, 29, 32 & 33.	
* No timber along river, except some stunted alders and willows fringing the bank and over hanging the water.	
N. bet. Secs. 28 & 29.	Var. 21° 6' E.
40.00 Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.	
80.00 Set post Cor. to Secs. 20, 21, 28 & 29; made mound and drove charred stake, as per instructions.	
Surface broken by ridges from 2 to 4 chs. apart and from 12 to 20 ft. in altitude, course E. & W.	