

Subdivisional Lines, T 5 N R 28 E W M.

Chains	
2.84	Bank of river, or shore.
3.30	2nd bank or bluff.
40.15	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
80.30	To Cor. of Secs. 17, 18 19 & 20.
<p>N. bet. Secs. 17 & 18.</p> <p style="text-align: right;">Var. 21°E.</p>	
Commence to descend.	
28.50	Columbia trail, course E. & W
30.00	Umatilla River, with bank, 12 ft. high, course N.40°W., width of stream, 6.00 chs.
38.00	Top of bank.
40.00	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
71.37	Set Meander Cor. post bet. Secs. 17 & 18, on bank of Columbia River, 2.50 chs. from water; made mound and drove charred stake, as per instructions.
<p>Umatilla Warehouse brs. N.68°E. about 5.00 chs. dist.</p> <p style="text-align: right;">Var.21°E.</p>	
<p>The land about the mouth of the Umatilla is not good, though better than most bordering the Columbia , but at best, it is very spotted as to fertility.</p>	
<p>W. on random line bet. Secs. 30 & 31.</p> <p style="text-align: right;">Var.21°25'E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.97	Intersect W. Bdy. of Tp., 3 lks. N. of Cor. to Secs. 30 & 31.
N.89°59' E. on true line bet. Secs. 30 & 31.	
39.97	Set $\frac{1}{4}$ Sec. post; made mound and drove charred stake, as per instructions.
79.97	To Cor. of Secs. 29, 30, 31 & 32.
<p>Surface; flat and gravelly</p> <p>Soil; sandy & gravelly and sage less abundant.</p>	