

Subdivision Sec.28, T 5 N R 28 E W M.

Chains

Retracing on true line S.0°15'E. from NW. Cor.
 20 Set stake for 16/3 Cor.
 40 Establish W ($\frac{1}{4}$) quarter Sec. Cor. and mark same with an
 iron pipe 1 in. diam., 24 ins. long, set 22 ins. in
 ground.
 60.00 Set stake for 16/4 Cor.
 80.01 SW. Cor. Sec. heretofore described.

From the SE. Cor. of Sec., an iron pipe, 2 ins. in diam.,
 projecting 12 ins. above ground, in place of and ac-
 cepted as original Cor. by settlers of developed reg-
 ion, no witnesses being now in evidence because of re-
 sulting changes, it being impracticable to run through
 on line to NE. Cor. of Sec., because of the rocky cliffs
 of Umatilla Butte rising, nearly vertical, in places,
 50 to 100 ft. on said line, I run N.08°11' E. and 53.02
 chs. set stake.

I set up over stake from which SE. Cor. of Sec. brs. S.08°
 11'W., 53.02 chs. and run N.15°39' W., 28.34 chs. to
 the NE. Cor. of Sec., an iron pipe, 2 ins. in diam.,
 projecting 2 ins. above ground in place of and accepted
 as original Cor. in fenced and developed region, wit-
 nesses having been obliterated by road grading and
 traffic.

Retracing from NE. Cor. of Sec. S.15°39' E., 28.34 chs.
 to stake from which I run S.08°11'W. and at

26.51 Set stake.

53.02 SE. Cor. Sec. marked as heretofore described.

I then set up at stake from which the SE. Cor. of Sec. brs.
 S.08°11' W. 26.51 chs. and run N.15°39'W., 14.17 chs. &
 established W. ($\frac{1}{4}$) quarter Cor. of Sec. and mark same
 with an iron pipe 1 in. in diam., 24 ins. long, set 22 ins.
 in ground.

Retracing S.15° 39' E.