

Subdivision Sec. 28, T 5 N R 28 E W M.

Chains	<p>From the 16/13 Cor. heretofore described, I run to the W. ($\frac{1}{4}$) quarter Cor. of Sec., which is visible, S. 89° 58' W.</p> <p>20.72 Intersect easterly right of way line of O-W R R & N Co., & marked same with iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.</p> <p>22.26 Intersect center line of track of O-W RR & N Co. and mark same with hub at Meander Cor.</p> <p>23.79 Intersect westerly right of way line of O-W RR & N Co. & mark same with an iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.</p> <p>40.21 W. ($\frac{1}{4}$) quarter Sec. Cor. of Sec. heretofore described.</p>
	<p>From the 16/16 Cor., heretofore described, I run to the 16/4 Cor. of Sec., which is visible, S. 89° 57' W.</p> <p>14.82 Intersect easterly right of way line of O-W RR & N Co., & mark same with iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.</p> <p>16.45 Intersect center line of track of O-W RR & N Co. and set hub at Meander Cor.</p> <p>18.08 Intersect westerly right of way line of O-W R R & N Co., & mark same with an iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.</p> <p>40.18 16/4 Cor. of Sec., heretofore described.</p>
	<p>From the S. ($\frac{1}{4}$) quarter section Cor., heretofore described, I run to the SW. Cor. of Sec., which is visible S. 89° 56' W.</p> <p>6.95 Intersect easterly right of way line of O-W RR & N Co., & mark same with iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.</p> <p>8.58 Intersect center line of tracks of O-W RR & N Co., and set hub at Meander Cor.</p> <p>10.20 Intersect westerly right of way line of O-W R R & N Co., & mark same with iron pipe, 1 in. diam., 24 ins. long, set 22 ins. in ground, for witness Cor. to Meander Cor.</p>