

Chains

40.14 SW.Cor. of Sec., marked as heretofore described.

Traverse of O-W RR & N Co's center line.

forming the Bdy. bet. Lots 1 & 2, 3 & 4, 5 & 6, 7 & 8.  
 From the Meander Cor. marked with hub at intersection of N.  
 line of Sec. and center line of track, from which, wit-  
 ness Cor. on easterly right of way line brs. S.89°59'E.  
 1.57 chs. and the witness Cor. on westerly right of way  
 line brs. N.89°59'W., 1.57 chs., also the N.¼ Cor. of  
 Secs. brs. S.89°59'E., 27.65 chs., & NW.Cor. of Sec. brs.  
 N.89°59' W., 12.62 chs., thence S.14°20' E.  
 (on tangent).

4.05 Beginning to curve to right of radius 5628 ft.(86.33) de-  
 flection or central angle being 9°35'. Mark same with  
 iron pipe, 1 in. diam., 24 ins. long, set 24 ins. in  
 ground.

Thence along said curve, measuring on 100 ft. chords.

14.42 End of curve and point of tangent. Mark same with iron pipe  
 1 in. diam., 24 ins. long, 24 ins. in ground.

Thence on tangent S.4°45'E.

1.86 Intersect Meander Cor., marked with hub at E. & W. center  
 line of NW¼ of Sec., from which witness Cor. on easter-  
 ly right of way line brs. N.89°59'E., 1.52 chs. and wit-  
 ness Cor. on westerly right of way line brs. S.89°59' W.,  
 1.52 chs.

14.64 Beginning of curve to left of radius 5730 ft.(86.82 chs.)  
 deflection or central angle being 16°41'. Mark same with  
 iron pipe, 1 in. diam., 24 ins. long, 24 ins. in ground.

Thence along said curve, measuring on 100 ft. chords.

7.32 Intersect Meander Cor., marked with hub at E. & W. center  
 line of Sec., from which witness Cor. on easterly right  
 of way line brs. N.89°58'E., 1.54 chs. and witness Cor.