

## Subdivision Sec.28, T 5 N R 28 E W M.

Chains	<p>on westerly right of way line brs. S.89°58' E., 1.54 chs., also the 16/13 Cor. brs. N.89°58'E., 22.26 chs. and the W.½ Cor. brs. S.89°58' W., 17.95 chs.</p> <p>25.30 End of curve and point of tangent. Mark same with iron pipe 1 in. diam., 24 ins. long, 24 ins. in ground.</p>
	<p>Thence on tangent S.21°26'E.</p> <p>2.92 Intersect Meander Cor., marked with hub at E. &amp; W. center line of SW¼ of Sec., from which witness Cor. on easterly right of way line brs. N.89°57'E., 1.63 chs. and witness Cor. on westerly right of way line brs. S.89°57' W., 1.63 chs.</p> <p>24.37 Intersect Meander Cor., marked with hub on S. line of Sec. from which witness Cor. on easterly right of way line brs. N.89°56'E., 1.63 chs. and witness Cor. on westerly right of way line brs. S.89°56'W., 1.62 chs., also the S½ Cor. brs. N.89°56'E., 8.58 chs. and the SW Cor. of Sec. brs. S.89°56'W., 31.56 chs.</p>