

## Subdivisional Lines, T 5 N R 29 E W M.

Chains	
80.16	To Cor. of Secs. 26, 27, 34 & 35.
	N. bet. Secs. 26 & 27.
40.00	<p style="text-align: right;">Var.21°E.</p> Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 22, 23, 26 & 27; made mound & drove charred stake, as per instructions.
	E. on random line bet. Secs. 23 & 26
40.00	<p style="text-align: right;">Var.20°30'E.</p> Set temp. $\frac{1}{4}$ Sec. post.
80.16	Intersect N. & S. line, 60 lks. N. of Sec. Cor. N.89°34'W. on true line bet. Secs. 23 & 26. Commence to descend.
40.08	Set $\frac{1}{4}$ Sec. Cor; made mound & drove charred stake, as per instructions.
80.16	To Cor. of Secs. 22, 23, 26 & 27. Surface of this mile is an inclined plane, as indicated in the margin.
	N. bet. Secs. 22 & 23.
5.00	<p style="text-align: right;">Var.20°30'E.</p> Strike rocky ground.
15.00	Walla Walla Trail, course N.E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
65.00	Commence ascending ledge of rocks.
70.00	Top of ledge, some perpendicular cliffs.
80.00	Set post Cor. to Secs. 14, 15, 22 & 23; made mound & drove charred stake, as per instructions.
	E. on random bet. Secs. 14 & 23.
	<p style="text-align: right;">Var.19°30'E.</p>