

Subdivisional Lines, T 5 N R 29 E W M.

Chains	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.25	Intersect N. & S. line, 34 lks. N. of Sec. Cor. N.89°45'W. on true line bet. Secs. 14 & 23.
40.12 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.25	To Cor. of Secs. 14, 15, 22 & 23.
N. bet. Secs. 14 & 15.	
Var.19 $\frac{1}{2}$ °E.	
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
Commence ascending.	
44.00	Top of rocky table.
67.00	N. side of rocky table.
80.00	Set post Cor. to Secs. 10, 11, 14 & 15, in Columbia Trail, from which A balm, 6 ins. diam., brs. N.2°W., 3.58 chs. dist. A balm, 12 ins. diam., brs. N.15°W., 3.42 chs. dist. Made mound & drove charred stake, as per instructions.
W. on true line bet. Secs. 10 & 15.	
5.00	Set post, Meander Cor. to Secs. 10 & 15, on bank of Columbia River, 12 ft. above & 1.50 chs. from the water; made mound of stone and deposited charred stake, as per instructions.
E. on random line bet. Secs. 11 & 14.	
Var.21°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.28	Intersect N. & S. line, 40 lks. N. of Sec. Cor. N.89°43'W. on true line bet. Secs. 11 & 14.
40.14	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.28	To Cor. of Secs. 10, 11, 14 & 15.