

## Subdivisional Lines, T 5 N R 29 E W M.

|         |   |
|---------|---|
| Chains. | Var.27°E.   |
|         | N. bet. Secs. 10 & 11.  |
| 3.38    | Set post, Meander Cor. to Secs. 10 & 11, from which<br>A balm, 6 ins. diam., brs. N.25°W., 50 lks. dist.<br>A balm, 12 ins. diam., brs. N.77°W., 94 lks. dist.<br>Made mound; deposited charred stake, as per instructions,<br>about 20 ft. above and 1.00 ch. dist. from the water<br>of the Columbia River. |
|         | Var.23°30'E.  |
|         | N. bet. Secs. 33 & 34.  |
|         | Var.20°45'E.  |
|         | Commence to descend.  |
| 24.50   | Walla Walla Trail, course N.E.  |
| 40.00   | Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per<br>instructions.  |
| 80.00   | Set Cor. post to Secs. 27, 28, 33 & 34; made mound & drove<br>charred stake, as per instructions.   |
|         | Var.21°10'E.  |
|         | E. on random bet. Secs. 27 & 34..   |
| 40.00   | Set temp. $\frac{1}{4}$ Sec. post.  |
| 80.12   | Intersect N. & S. line, 17 lks. N. of Sec. Cor.<br>N.89°53'W. on true line bet. Secs. 27 & 34.<br>Commence descending.  |
| 40.06   | Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per<br>instructions.  |
| 51.12   | Walla Walla Trail, course N.E.  |
| 80.12   | To Cor. of Secs. 27, 28, 33 & 34.<br>Surface of this mile nearly flat. Soil; sandy.   |
|         | N. bet Sunday Sept. 22, 1861.   |
|         | N. bet. Secs. 27 & 28.  |
|         | Var.21°E.   |
| 40.00   | Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per<br>instructions.  |