

Subdivisional Lines, T 5 N R 29 E W M.

Chains	
80.00	Set post Cor. to Secs. 21, 22, 27 & 28; made mound & deposited charred stake, as per instructions. Surface nearly flat with small sand ridges, course E. & W.
	Var. 21° E.
	E. on random bet. Secs. 22 & 27.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line, 30 lks. N. of Sec. Cor. N. 89° 47' W. on true line bet. Secs. 22 & 27.
9.00	Walla Walla Trail, course N.E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	To Cor. of Secs. 21, 22, 27 & 28.
	N. bet. Secs. 21 & 22.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
76.50	Columbia Trail, N.E. course.
80.00	Set post Cor. to Secs. 15, 16, 21 & 22. The surface of this mile is broken & rocky.
	Var. 21° E.
	E. on random bet. Secs. 15 & 22.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line at the Sec. Cor. W. on true line bet. Secs. 15 & 22.
28.40	Edge of rocky table land.
31.33	Descend rocky table, course N.E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
69.00	Columbia Trail, course N. 50° E.
80.00	To Cor. of Secs. 15, 16, 21 & 22.
	N. bet. Secs. 15 & 16.
	Var. 21° E.