

## Subdivisional Lines, T 5 N R 29 E W M.

Chains	
2.00	Intersect perpendicular table of rock, 50 ft. high & $\frac{1}{2}$ mile long, course of table N.65°E. Dist. to western extremity 2.00 chs.
9.93	Descend rocky table.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
47.00	Perpendicular rock table.
61.00	Commence to descend bluff by ledges & benches.
66.77	Set post, Meander Cor. to Secs. 15 & 16, on bank of the Columbia River, about 80 or 100 ft. above water; made mound & drove charred stake, as per instructions. Var.29°15'E.
N. bet. Secs. 32 & 33.	
Var.20°40'E.	
10.00	Descend bank into flat, apparently the receptacle of "Dry Run".
25.00	Leave clay flat.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 28, 29, 32 & 33; made mound & drove charred stake, as per instructions.
Var.20°40'E.	
E. on random bet. Secs. 28 & 33.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.13	Intersect N. & S. line at Sec. Cor.
W. on true line bet. Secs. 28 & 33.	
40.06 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.13	To Cor. of Secs. 28, 29, 32 & 33.
Surface; slightly undulating.	
Soil; less sandy. Grass good.	