

Subdivisional Lines, T 5 N R 29 E W M.

Chains

N. bet. Secs. 28 & 29.

Var. 20°40'E.

40.00 Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.

80.00 Set post Cor. to Secs. 20, 21, 28 & 29; made mound & drove charred stake, as per instructions.

Surface of this mile, undulates in sand banks & ridges.

Var. 21°E.

E. on random line bet. Secs. 21 & 28.

40.00 Set $\frac{1}{4}$ Sec. post, temporarily.

80.00 Intersect N. & S. line at Sec. Cor.

W. on true line bet. Secs. 21 & 28.

40.05 Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.

80.10 To Cor. of Secs. 20, 21, 28 & 29.

N. bet. Secs. 20 & 21.

Var. 21°E.

40.00 Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.

40.50 Columbia Trail, course W.

80.00 Set post Cor. to Secs. 16, 17, 20 & 21; made mound & drove charred stake, as per instructions.

Surface of this mile is broken, ridged & rocky. Soil is sand.

Var. 21°E.

E. on random line bet. Secs. 16 & 21.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.90 Intersect N. & S. line, 34 lks. N. of Sec. Cor.

N. 89°45'W. on true line bet. Secs. 16 & 21.

39.95 Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.

79.90 To Cor. of Secs. 16, 17, 20 & 21. Surface of this mile is broken & rocky.