

Subdivisional Lines, T 5 N R 29 E W M.

Chains	N. bet. Secs. 16 & 17.
	Var. 20°21'E.
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
65.00	Commence to descend bank of the Columbia River.
72.50	Set post, Meander Cor. to Secs. 16 & 17, on bank of Columbia, 10 ft. above and 1.00 ch. dist. from the water, opposite a gravelly island, some 40.00 chs. long & built mound of stone, with charred stake, as per instructions.
	Monday Sept. 23, 1861.
	N. bet. Secs. 31 & 32.
	Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post ; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 29, 30, 31 & 32; made mound & drove charred stake, as per instructions.
	Surface of this mile lies in sand ridges, from 10 to 12 ft. high.
	E. on random line bet. Secs. 29 & 32.
	Var. 21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.37	Intersect N. & S. line, 24 lks. N. of Sec. Cor. N. 89°50'W. on true line bet. Secs. 20 & 32.
40.18 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.37	To Cor. of Secs. 29, 30, 31 & 32.
	W. on random bet. Secs. 30 & 31.
	Var. 21°E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.60	Intersect W. Bdy. of Tp., 24 lks. S. of Sec. Cor. S. 89°50'E. on true line bet. Secs. 30 & 31.
40.60	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per.