

Subdivisional Lines, T 5 N R 29 E W M.

Chains

instructions.

80.60 To Cor. of Secs. 29, 30, 31 & 32.

N. bet. Secs. 29 & 30.

Var.21°E.

40.00 Set post Cor. to $\frac{1}{4}$ Sec.; made mound & drove charred stake as per instructions.

80.00 Set post Cor. to Secs. 19, 20, 29 & 30; made mound & drove charred stake, as per instructions.

Surface of this mile lies in small sand waves or ridges.

Var.21°30'E.

E. on random line bet. Secs. 20 & 29.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.52 Intersect N. & S. line, 20 lks. N. of the Sec. Cor. to Secs. 20, 29, 21 & 28.

N.89°51'W. on true line bet. Secs. 20 & 29.

40.26 Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.

80.52 To Cor. of Secs. 19, 20, 29 & 30.

Surface of this mile is nearly level. Soil is sand.

W. on random bet. Secs. 19 & 30.

Var.21°30'E.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.62 Intersect W. Bdy. of Tp., 37 lks. S. of Cor. to Secs. 19 & 30.

S.89°44'E. on true line bet. Secs. 19 & 30.

40.62 Set post $\frac{1}{4}$ Sec. Cor.; made mound & drove charred stake, as per instructions.

80.62 To Cor. of Secs. 19, 20, 29 & 30.

Var.21°30'E.

N. bet. Secs. 19 & 20.