

Subdivisional Lines, T 5 N R 29 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
41.00	Columbia Trail, course E.& W.
45.00	Enter rocky ground.
80.00	Set post Cor. to Secs. 17, 18, 19 & 20; made mound & drove charred stake, as per instructions.
E. on random line bet. Secs. 17 & 20. Var. 20°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.50	Intersect N. & S. line, 24 lks. N. of post Cor. to Secs. 16, 17, 20 & 21. N. 89°50'W. on true line bet. Secs. 17 & 20.
40.25	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.50	To Cor. of Secs. 17, 18, 19 & 20.
W. on random bet. Secs. 18 & 19.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.70	Intersect W. Bdy. of Tp., 54 lks. S. of Sec. Cor. S. 89°37'E. on true line bet. Secs. 18 & 19.
40.70	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.70	To Cor. of Secs. 17, 18, 19 & 20. Surface of this mile is nearly flat and very rocky.
N. bet. Secs. 17 & 18. Var. 20°E.	
40.00	Set $\frac{1}{4}$ Sec. post; made mound & drove charred stake, as per instructions.
80.00	Set post Cor. to Secs. 7, 8, 17 & 18; made mound & drove charred stake, as per instructions. Surface flat & rocky.