

East Bdy., T 5 N R 30 E W M.

Chains	N. bet. Secs. 13 & 18.
	Var. 19°50'E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor. and build mound of earth, with pits, trench, etc., as per instructions.
80.00	Set post for Cor. to Secs. 12, 13, 7 & 18, and build mound of earth, with pits, trench, etc., as per instructions. Land; gently rolling. Soil; 3rd rate, sandy.
	Aug. 9th, 1859.
	N. bet. Secs. 7 & 12.
	Var. 18°10'E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., and build mound of earth, with pits, trench, etc., as per instructions.
80.00	Set post for Cor. to Secs. 1, 12, 6 & 7, and build mound of earth, with pits, trench, etc., as per instructions. Land; gently rolling. Soil; very poor and sandy.
	Aug. 9th, 1859.
	N. bet. Secs. 1 & 6.
	Var. 19°50'E.
40.00	Set post for $\frac{1}{4}$ Sec. Cor., and build mound of earth, with pits, trench, etc., as per instructions.
76.00	Descend hill.
80.00	Set post for Cor. to Tps. 5 & 6 N., Rs. 30 & 31 E., from which A juniper, 24 ins. diam., brs. N. 8 $\frac{1}{2}$ °E., 300 lks. dist. A " 20 " " " S. 69 $\frac{1}{2}$ °E., 550 lks. " . There being no other trees convenient, I deposited $\frac{1}{2}$ gal. charcoal and charred stake. The soil is so loose and sandy that mound cannot be built. There are no prominent peaks, point of rock or other notable object that can be taken from the course, which is on S. slope of deep canyon, which brs. E. & W., in which