

Subdivisional Lines, T 5 N R 30 E W M.

| Chains | |
|--------|---|
| 80.24 | Intersect Sec. line, 25 lks. N. of Cor. to Secs. 25, 26, 35 & 36. |
| | N.89°50'W. on true line bet. Secs. 25 & 35. |
| 40.12 | Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.24 | Cor. to Secs. 26, 27, 34 & 35. |
| | N. on line bet. Secs. 26 & 27. |
| 5.00 | Top of hill, descending into ravine. |
| 20.00 | Bottom of ravine, about 150 ft. deep, course W. |
| 32.00 | Top of hill. |
| 40.00 | Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.00 | Set charred stake, with mound, trench & pits, as per instructions for Cor. to Secs. 22, 23, 26 & 27. |
| | Var. 20°24'E. |
| | Land; uneven. |
| | Soil; sandy, 3rd rate. |
| | E. on random line bet. Secs. 23 & 26. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. Cor. |
| 80.40 | Intersect Sec. line, 18 lks. N. of post Cor. to Secs. 23, 24, 25 & 26. |
| | N.89°57'W. on true line bet. Secs. 23 & 26. |
| 40.20 | Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.40 | Cor. to Secs. 22, 23, 26 & 27. |
| | Soil; 2nd rate. |
| | N. on line bet. Secs. 22 & 23. |
| 40.00 | Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor. |
| 80.00 | Set charred stake, with mound, trench & pits, as per instructions, for Cor. to Secs. 14, 15, 22 & 23. |