

## Subdivisional Lines, T 5 N R 30 E W M.

Chains	
	<p>structions, for Cor. to Secs. 4, 5, 8 &amp; 9. Var. 20°E.</p> <p>Surface; uneven. Soil; 3rd rate.</p>
	<p>E. on random bet. Secs. 4 &amp; 9.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.60	Intersect Sec. line, 35 lks. N. of post Cor. to Secs. 3, 4, 9 & 10. N. 89°45'W. on true line bet. Secs. 4 & 9.
40.30	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.60	Cor. to Secs. 4, 5, 8 & 9. Land; broken. Soil; 3rd rate.
	<p>N. on true line bet. fractional Secs. 4 &amp; 5.</p>
26.50	Trail & river bottom, N. 70°E.
30.78	River bank. Set charred stake, with mound, trench & pits, as per instructions, for Meander Cor. to fractional Secs. 4 & 5. Var. 19°30'E.
	<p>N. on line bet. Secs. 31 &amp; 32. Var. 20°15'E.</p>
32.50	Begin to descend into ravine, course S. 80°W.
40.00	Set charred stake, with mound, trench & pits, as per instructions, for $\frac{1}{4}$ Sec. Cor.
49.50	Bottom of ravine about 80 ft. deep.
58.00	Top of hill.
80.00	Set charred stake, with mound, trench & pits, as per instructions for Cor. to Secs. 29, 30, 31 & 32. Var. 19°54'E. Soil; rather sandy, 3rd rate.