

Subdivisional Lines, T 5 N R 31 E W M.

Chains

80.42	The Cor. Land; rolling. Soil; 1st rate. Good grass.
N. bet. Secs. 11 & 12. Var. 21°30'E.	
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 1, 2, 11 & 12. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 1st rate. Good grass.
E. on random line bet. Secs. 1 & 12.	
40.00	Set temp. $\frac{1}{4}$ Sec; Cor.
79.53	Intersect E. Bdy. of Tp., 262 lks. S. of Cor. S. 88°08' W. on true line.
39.76	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
79.53	The Cor. Land; rolling. Soil; 1st rate. Good grass.
N. on random line bet. Secs. 1 & 2. Var. 20°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
78.70	Intersect N. Bdy. of Tp., 348 lks. E. of Cor. S. 2°28'E. on true line.
38.70	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
78.70	The Cor. Land; rolling. Soil; 1st Rate. Good grass. Note: See resurvey of Exterior Bdys. of this Tp.