

## Subdivisional Lines, T 5 N R 31 E W M.

| Chains |  |
|--------|--|
|        | <p>N. bet. Secs. 34 &amp; 35.</p> <p>40.00 Drove charred stake &amp; raised mound of earth, with pits, etc.,<br/>as per instructions, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>79.75 Bed of Spring Water Canyon, course S.W.</p> <p>80.00 Set basalt stone, 12 x 10 x 7, 6 ins. in ground, for Cor. to<br/>Secs. 26, 27, 34 &amp; 35.</p> <p>Land; rolling. Soil; 1st rate. Good grass.<br/>Fresh water spring, 50 lks. S.W. of Cor.</p>  |
|        | <p>E. on random line bet. Secs. 26 &amp; 35.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p> <p>80.30 Intersect N. &amp; S. line, 239 lks. N. of Cor.<br/>N. 88° 18' W. on true line.</p> <p>40.15 Drove charred stake &amp; raised mound of earth, with pits, etc.,<br/>as per instructions, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>80.00 Enter Spring water Canyon, course S W.</p> <p>80.30 The Cor.</p> <p>Land; rolling.<br/>Soil; 1st rate. Good grass.<br/>Note: See resurvey of Exterior Bdys. of this Tp.</p>  |
|        | <p>N. bet. Secs. 26 &amp; 27.</p> <p style="text-align: right;">Var. 21° E.</p> <p>40.00 Drove charred stake &amp; raised mound of earth, with pits, etc.<br/>as per instructions, for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>58.00 Ravine, course S.W.</p> <p>80.00 Drove charred stake &amp; raised mound of earth, with pits, etc.,<br/>as per instructions, for Cor. to Secs. 22, 23, 26 &amp; 27.</p> <p>Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit.</p> <p>Land; rolling.<br/>Soil; 1st rate. Good grass.</p> <p style="text-align: right;">Oct. 26, 1874.</p> |