

Subdivisional Lines, T 5 N R 31 E W M.

Chains	E. on random line bet. Secs. 23 & 26..
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.28	Intersect N. & S. line, 185 lks. N. of Cor. N.88°41' W. on true line.
32.00	Ravine, course S.W.
40.14	Set basalt stone, 16 x 10 x 5, 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
80.28	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	N. bet. Secs. 22 & 23. Var.22°E.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 14, 15, 22 & 23. Drove fir stke, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate, good grass.
	E. on random line bet. Secs. 14 & 23.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.05	Intersect N. & S. line, 194 lks. N. of Cor. N.88°37'W. on true line.
40.03	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.05	The Cor. Land; gently rolling. Soil; 1st rate, good grass.
	N. bet. Secs. 14 & 15. Var.21°30'E.
40.00	Drove charred stake & raised mound of earth, with pits, etc.,