

Subdivisional Lines, T 5 N R 31 E W M.

Chains

N. on random line bet. Secs. 2 & 3.

Var. 21°15'E.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

76.38 Intersect N. Bdy. of Tp., 369 lks. E. of Cor.

S. 2°38' E. on true line.

36.38 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for $\frac{1}{4}$ Sec. Cor.

76.38 The Cor.

Land; rolling.

Soil; 1st rate. Good grass.

N. bet. Secs. 33 & 34.

40.00 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for $\frac{1}{4}$ Sec. Cor.

51.50 Spring Water Canyon, course N.W.

60.00 Ravine, course S.W.

80.00 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for Cor. to Secs. 27, 28 33 & 34.

Drove pine stake, 2 ft. long, 2 ins. sq., in S.E. pit.

Land; rolling.

Soil; 1st rate, good grass.

Oct. 27th, 1874.

E. on random line bet. Secs. 27 & 34.

40.00 Set temp. $\frac{1}{4}$ Sec. Cor.

80.40 Intersect N. & S. line at Cor.

W. on true line.

40.20 Drove charred stake & raised mound of earth, with pits, etc.,
as per instructions, for $\frac{1}{4}$ Sec. Cor.

80.40 The Cor.

Land; rolling.

Soil; 1st rate. Good grass.

N. bet. Secs. 27 & 28.

Var. 21°E.

40.00 Set basalt stone, 14 x 8 x 6, 7 ins. in ground, for $\frac{1}{4}$ Sec. Cor.