

Subdivisional Lines, T 5 N R 31 E W M.

Chains	E. on random line bet. Secs. 17 & 20.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.35	Intersect N. & S. line, 249 lks. N. of Cor. N. $88^{\circ}13'$ W. on true line.
40.17	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.35	The Cor. Land; rolling. Soil; 1st rate. Good grass.
<hr/>	
	W. on random line bet. Secs. 18 & 19.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.43	Intersect W. Bdy. of Tp., 100 lks. S. of Cor. S. $89^{\circ}17'$ E. on true line.
40.43	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.43	The Cor. Land; rolling. Soil; 1st rate. Good grass.
<hr/>	
	N. bet. Secs. 17 & 18. Var. 21° E.
40.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake; raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 7, 8, 17 & 18. Drove willow stake, 2 ft. long, 2 ins. sq., in S. E. pit. Land; rolling. Soil; 1st rate.
<hr/>	
	E. on random line bet. Secs. 8 & 17.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.00	Intersect N. & S. line, 238 lks. N. of Cor. N. $88^{\circ}18'$ W. on true line.