

Resurvey Exterior Lines, T 5 N R 32 E W M.

Chains	
85.05	A point, 305 lks. N. of Cor. to Tps. 5 & 6 N., Rs. 31 & 32 E. Nov. 3rd, 1874.
	Subdivisional Lines, T 5 N R 32 E W M. As surveyed by same Surveyor, Under same Contract & date.
	From Cor. of Secs. 35 & 36, on S. Bdy. of Tp., I run N. bet. Secs. 35 & 36.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for Cor. to Secs. 25, 26, 35 & 36. Drove alder stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; gently rolling. Soil; 1st rate. Good grass.
	E. on random line bet. Secs. 25 & 36.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.53	Intersect E. Bdy. of Tp., 15 lks. S. of Cor. S.89°54' W. on true line.
40.26	Drove charred stake & raised mound of earth, with pits, etc., as per instructions for $\frac{1}{4}$ Sec. Cor.
80.53	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	N. bet. Secs. 25 & 26. Var. 20°45' E.
16.50	Enter flat, brs. N.E. & S.W.
35.00	Leave flat, brs. N.E. & S.W.
40.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake & raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 23, 24, 25 & 26.