

Subdivisional Lines, T 5 N R 32 E W M.

Chains

Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.  
Land; rolling.  
Soil; 1st rate. Good grass.

E. on random line bet. Secs. 22 & 27.

40.00 Set temp.  $\frac{1}{4}$  Sec. Cor.

80.96 Intersect N. & S. line, 190 lks. N. of Cor.  
N.88°39' W. on true line.

38.00 Enter flat, brs. N.W. & S.E.

40.48 Drove charred stake and raised mound of earth, with pits,  
etc., as per instructions, for  $\frac{1}{4}$  Sec. Cor.

69.00 Leave flat, brs. N.W. & S.E.

80.96 The Cor.

Land; flat level, upland-gently rolling.

Soil; 1st rate.

N. bet. Secs. 21 & 22.

Var.21°30'E.

10.00 Enter flat, brs. N.W. & S.E.

30.00 Leave flat, brs. N.W. & S.E.

40.00 Drove charred stake and raised mound of earth, with pits,  
etc., as per instructions, for  $\frac{1}{4}$  Sec. Cor.

80.00 Drove charred stake and raised mound of earth, with pits,  
etc., as per instructions, for Cor. to Secs. 15, 16,  
21 & 22.

Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit.

Land; gently rolling.

Soil; 1st rate.

E. on random line bet. Secs. 15 & 22.

40.00 Set temp.  $\frac{1}{4}$  Sec. Cor.

80.85 Intersect N. & S. line, 175 lks. N. of Cor.  
N.88°45' W. on true line.

40.42 Drove charred stake and raised mound of earth, with pits,