

## Subdivisional Lines, T 5 N R 32 E W M.

Chains	<p>Drove willow stake, 2 ft. long, 2 ins. sq., in S.E.pit. Land; gently rolling. Soil; 1st rate.</p>
	<p>E. on random line bet. Secs. 3 &amp; 10</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.78	Intersect N. & S. line, 140 lks. N. of Cor. N.89° W. on true line.
40.39	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
54.75	Leave juniper Canyon, course N.W.
80.78	The Cor. Land; gently rolling. Soil; 1st rate.
	<p>N. on random line bet. Secs. 3 &amp; 4. Var.21°30'E.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
83.36	Intersect N. Bdy. of Tp., 210 lks. E. of Cor. S.1°30' E. on true line.
43.36	Set basalt stone, 12 x 10 x 8, 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor.
62.00	Bed of Juniper Canyon, course W.
83.36	The Cor. Land; rolling. Soil; 1st rate. Good grass.
	<p>N. bet. Secs. 32 &amp; 33.</p>
15.00	Spring Water Canyon, course W.
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 28, 29, 32 & 33.