

Subdivisional Lines, T 5 N R 32 E W M.

Chains	S.88°44' E. on true line.
6.00	Leave Spring Water Canyon, course N.W.
40.02	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.02	The Cor. Land; rolling. Soil; 1st rate.
N. bet. Secs. 29 & 30.	
Var.22°E.	
40.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.00	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for Cor. to Secs. 19, 20, 29 & 30. Drove willow stake, 2 ft. long, 2 ins. sq., in S.E. pit. Land; rolling. Soil; 1st rate. Good grass.
E. on random line bet. Secs. 20 & 29.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.90	Intersect N. & S. line, 35 lks. S. of Cor. S.89°45' W. on true line.
40.45	Drove charred stake and raised mound of earth, with pits, etc., as per instructions, for $\frac{1}{4}$ Sec. Cor.
80.90	The Cor. Land; rolling. Soil; 1st rate.
W. bet. Secs. 19 & 30, on random line.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor. Var. 12°30' E.
79.47	Intersect W. Bdy. of Tp., 296 lks. S. of Cor., with pits, S.87°53' E. on true line, for $\frac{1}{4}$ Sec. Cor.
39.47	Drove charred stake and raised mound of earth, with pits,