

1.

Exterior Lines, T 5 N R 33 E W M.  
 As surveyed by Wm. H. Odell & Wm. L. Lewis, U.S. Depty. Surveyors  
 Under Contract No. 110,  
 Dated Feby. 7th, 1865.

Chains	
	April 18th, 1865.
	N. bet. Rs. 33 & 34 E., T 5 N., on E. Bdy. of Sec. 36.
40.00	Set $\frac{1}{4}$ Sec. post on land, sloping E. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. to Secs. 25, 36, 30 & 31, land slopes to SE. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken, good grass. Soil; 2nd rate.
	N. on E. Bdy. of Sec. 25, T 5 N R 33 E. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. Cor., on level. Drove charred stake ; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 24, 25, 19 & 30, on level. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Good grass. Soil; good 2nd rate.
	N. on E. Bdy. of Sec. 24, T 5 N. R 33 E. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post on level. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 13, 24, 18 & 19, on level. Drove charred stake; dug pits & raised mound, as per instructions. Land; gently rolling. Good grass. Soil; good 2nd rate.