

## Subdivisional Lines, T 5 N R 33 E W M.

Chains	
80.25	To post Cor. Land; rolling, Grass good. Soil; 2nd rate.
<p>N. on random bet. Secs. 1 &amp; 2, T 5 N R 33 E.  Var. 21° E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.75	Intersect E. & W. Tp. line, 28 lks. E. of post, from which I run
S. 12' E. on true line.	
40.75	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.75	To post Cor. Land; broken. Soil; 2nd rate. Grass good.
<p>N. bet. Secs. 34 &amp; 35, T 5 N R 33 E.  Var. 21° E.</p>	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor., for Secs. 26, 27, 34 & 35. Drove charred stake; dug pits & raised mound, as per instructions. Land; rolling. Soil; 2nd rate. Grass good.
<p>E. on random bet. Secs. 26 &amp; 35, T 5 N R 33 E.</p>	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.09	Intersect N. & S. line, 20 lks. S. of post, from which I run
S. 89° 51' W. on true line.	
40.04	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
80.09	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.