

Subdivisional Lines, T 5 N R 33 E.

Chains	E. on random bet. Secs. 14 & 23.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.88	Intersect N. & S. line, 25 lks. N. of post, from which I run N.89°49' W. on true line.
39.94	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per in- structions.
79.88	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
	N. bet. Secs. 14 & 15. Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per in- structions.
80.00	Set post Cor. for Secs.10, 11, 14 & 15. Drove charred stake; dug pits & raised mound, as per in- structions. Land; rolling. Grass good. Soil; 2nd rate.
	E. on random bet. Secs. 11 & 14:
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.80	Intersect N. & S. line, 40 lks. N. of post, from which, I run N.89°43'W. on true line.
39.90	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
79.80	To post Cor. Land; rolling. Soil; 2nd rate. Grass good.