

Subdivisional Lines, T 5 N R 33 E W M.

Chains	E. on random bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.60	Intersect N. & S. line, 55 lks. S. of post, from which I run S.89°36' W. on true line.
39.80	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.60	To post Cor. Land; rolling. Grass good. Soil; 2nd rate.
<hr/>	
	N. bet. Secs. 28 & 29. Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. to Secs. 20, 21, 28 & 29, in Canyon at foot of hill, facing S. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass good. Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 21 & 28.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line, 20 lks. N. of post, from which I run N.89°51'W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post; dug pits; drove charred stake & raised mound, as per instructions.
80.00	To post Cor. Land; rolling. Soil; 2nd rate. Good grass.
<hr/>	