

## Subdivisional Lines, T 5 N R 33 E W M.

Chains	
79.65	To post Cor. Land; rolling. Soil; 2nd rate. Grass good.
N. bet. Secs. 17 & 18.	
Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post in ravine, course N. , for Secs. 7, 8, 17 & 18. Drove charred stake; dug pits and raised mound, as per instructions. Land; rolling. Soil; 2nd rate. Grass good.
E. on random bet. Secs. 8 & 17.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line, 20 lks. S. of post, from which I run S. 89° 51' W, on true line.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound as per instructions.
80.00	To post Cor. Land; rolling. Soil; 2nd rate. Grass good.
W. on random line bet. Secs. 7 & 18.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.85	Intersect N. & S. Tp. line, 50 lks. S. of post, from which I run S. 89° 38' E. on true line.
39.85	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.
79.85	To post Cor.