

Exterior Lines, T 5 N R 34 E W M.

Chains	
69.50	Road, course N.E. & S.W.
80.00	Set post Cor. for Secs. 12, 13, 7 & 18, on hillside, sloping to N. Drove charred stake; dug pits and raised mound, as per instructions. Land; hilly. Good grass. Soil; 2nd rate.
40.00	N. on E. Bdy. of Sec. 12. Var. 21° E. Set $\frac{1}{2}$ Sec. Post on hillside, facing N. Drove charred stake; dug pits and raised mound, as per instructions.
75.00	Pine Creek, course N.W.
80.00	Set post Cor., for Secs. 7, 12, 1 & 6. Dug pits; drove charred stake and raised mound, as per instructions. Land; hill. Grass poor. Soil; 3rd rate.
40.00	N. on E. Bdy. of Sec. 1. Var. 21° E. Set $\frac{1}{2}$ Sec. post Cor. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor., for Tps. 5 & 6 N., Rs. 34 & 35 E., Secs. 1, 6, 31 & 36. Land slopes to N. Drove charred stake; dug pits and raised mound, as per instructions. Land; hill. Fair grass. Soil; 3rd rate.
	April 11th, 1865. W. bet. Tps. 5 & 6 N., Rs. 34 E. on N. Bdy. of Secs. 1, T 5 N. Var. 21° E. Set $\frac{1}{2}$ mile and mile posts at 40.00 and 80.00 chs. and find the Tp. line to be 5 miles, 78.44 chs. and the falling