

Subdivisional Lines, T 5 N R 34 E W M.

Chains

N. bet. Secs. 35 & 36.

Var. 20°E.

1.50 Trail, course E. of N.

40.00 Set $\frac{1}{4}$ Sec. post Cor.

Drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 25, 26, 35 & 36.

Land sloping to the W.

Drove charred stake; dug pits and raised mound, as per instructions.

Land; rolling.

Good grass.

Soil; 2nd rate.

E. on random bet. Secs. 25 & 36.

9.50 A trail, course E. of N.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.30 Intersect N. & S. line, 25 lks. S. of post, Cor. for Secs. 25, 36, 31 & 30, from which I run

S. 89°49' W. on true line.

40.15 Set $\frac{1}{4}$ Sec. Cor. post, land sloping to S.E.

Drove charred stake; dug pits and raised mound, as per instructions.

80.30 To post Cor.

Land; rolling.

Good grass.

Soil; good 2nd rate.

N. bet. Secs. 25 & 26.

Var. 21°E.

40.00 Set $\frac{1}{4}$ Sec. post Cor., on level; drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 24, 25, 26 & 23, on level. Drove charred stake; dug pits and raised mound, as per instructions.