

Subdivisional Lines, T 5 N R 34 E W M.

Chains

58.00 Trail, course N.
 80.10 Intersect N. & S. line at post, from which I run
 W. on true line.
 40.05 Set $\frac{1}{4}$ Sec. post Cor., on side hill, facing the W.
 Drove charred stake; dug pits and raised mound, as per
 instructions.
 80.10 To post Cor.
 Land; broken.
 Good grass.
 Soil; 2nd rate.

N. bet. Secs. 13 & 14.

Var. 21°E.

40.00 Set $\frac{1}{4}$ Sec. post, land slopes to E.
 Drove charred stake; dug pits and raised mound, as per
 instructions.

Var. 20°E.

80.00 Set post Cor. for Secs. 11, 12, 13 & 14, on side hill,
 facing W.
 Drove charred stake; dug pits and raised mound, as per
 instructions.
 Land; broken.
 Good grass.
 Soil; 2nd rate.

E. on random bet. Secs. 12 & 13.

40.00 Set $\frac{1}{4}$ Sec. temp. post.
 79.93 Intersect N. & S. line, 27 lks. N. of post, Cor. for Secs.
 12, 13, 7 & 18, from which I run
 N. 89°48' W. on true line.
 39.96 Set $\frac{1}{4}$ Sec. post Cor. on hill side, facing the E. Drove
 charred stake; dug pits and raised mound, as per in-
 structions.
 79.93 To post.
 Land; very broken. Soil; hardly 2nd rate.