

Subdivisional Lines, T 5 N R 34 E W M.

Chains	
79.70	Intersect N. & S. line, 30 lks. N. of post Cor. for Secs. 23, 24, 25 & 26, from which I run N.89°47'W. on true line.
39.85	Set $\frac{1}{4}$ Sec. post Cor., on level. Drove charred stake; dug pits and raised mound, as per instructions.
79.70	To post Cor. Land; rolling. Good grass. Soil; good 2nd rate.
N. bet. Secs. 22 & 23.	
Var.21°E.	
40.00	Set $\frac{1}{4}$ Sec. post, on level. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 14, 15, 22 & 23, on level. Land; gently rolling. Good grass. Soil; good 2nd rate.
April 12, 1865.	
E. on random bet. Secs. 14 & 23.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.58	Intersect N. & S. line, 42 lks. N. of post, from which, I run N.89°42'W. on true line.
39.79	Set $\frac{1}{4}$ Sec. post, on level. Drove charred stake; dug pits and raised mound, as per instructions.
79.58	To post Cor.
?(79.85)	Land; gently rolling. Good grass. Soil; 2nd rate.
N. bet. Secs. 14 & 15.	
Var.21°E.	
40.00	Set $\frac{1}{4}$ Sec. post, land sloping to S.E. Drove charred stake;