

Subdivisional Lines, T 5 N R 34 E W M.

| | |
|---------|--|
| Chains. | dug pits and raised mound, as per instructions. |
| 80.00 | Set post Cor. for Secs. 10, 11, 14 & 15, on steep hillside sloping to N. Drove charred stake; dug pits and raised mound, as per instructions. Good grass. Soil; 2nd rate. Land; on last half, descending. |
| | E. on random bet. Secs. 11 & 14. |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post. |
| 79.84 | Intersect N. & S. line, 20 lks. N. of post Cor. for Secs. 11, 12, 13 & 14, from which, I run N.89°51'W. on true line. |
| 39.92 | Set $\frac{1}{4}$ Sec. post Cor. on side hill, facing N. Drove charred stake; dug pits and raised mound; as per instructions. |
| 79.84 | To post Cor. Land; broken. Soil; hardly 2nd rate. |
| | N. bet. Secs. 10 & 11. Var. 21°E. |
| 40.00 | Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions. |
| 80.00 | Set post Cor. for Secs. 2, 3, 10 & 11. Drove charred stake dug pits and raised mound, as per instructions. Land; broken. Soil; hardly 2nd rate. |
| | E. on random bet. Secs. 2 & 11 |
| 40.00 | Set temp. $\frac{1}{4}$ Sec. post. |
| 78.48 | Intersect N. & S. line, 10 lks. S. of post Cor. for Secs. 1, 2, 11 & 12, from which I run S.89°56'W. on true line. |