

Subdivisional Lines, T 5 N R 34 E W.M.

Chains

S.89°43'W. on true line.

39.85 Set $\frac{1}{4}$ Sec. post in ravine. Drove charred stake; dug pits
and raised mound, as per instructions.

79.70 To post Cor.
Land; rolling.

Grass good.

Soil; good 2nd rate.

N. bet. Secs. 27 & 28.

Var.20°E.

40.00 Set $\frac{1}{4}$ Sec. post, on level. Drove charred stake; dug pits
and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 21, 22, 27 & 28. Drove charred stake
dug pits and raised mound, as per instructions.

Land; broken.

Soil; 2nd rate.

Grass good.

E. on random bet. Secs. 22 & 27.

40.00 Set $\frac{1}{4}$ Sec. post, temporarily.

79.92 Intersect N. & S. line, 26 lks. S. of post, from which, I
run

S.89°49' W. on true line.

39.96 Set $\frac{1}{4}$ Sec. post.

Land slopes to S.E.

Drove charred stake; dug pits and raised mound, as per in-
structions.

79.92 To post Cor.

Land; broken.

Grass good.

Soil; 2nd rate, good.

N. bet. Secs. 21 & 22.

Var.20°E.