

Subdivisional Lines, T 5 N R 34 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post Cor., on level; drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 15, 16, 21 & 22, on level. Drove charred stake; dug pits and raised mound, as per instructions.
	Land; gently rolling.
	Good grass.
	Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 15 & 22.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.50	Intersect N. & S. line, 46 lks. S. of post, from which, I run S.89°40' W. on true line.
39.75	Set $\frac{1}{4}$ Sec. post Cor., on level. Drove charred stake; dug pits & raised mound, as per instructions.
79.50	To post Cor.
	Land; gently undulating.
	Good grass.
	Soil; good 2nd rate.
<hr/>	
	N. bet. Secs. 15 & 16.
	Var. 20° E.
40.00	Set $\frac{1}{4}$ Sec. post Cor., on level. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. to Secs. 9, 10, 15 & 16. Drove charred stake; dug pits and raised mound, as per instructions. This line passes down steep hill, good grass.
	Soil; 2nd rate.
<hr/>	
	E. on random bet. Secs. 10 & 15.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.
79.74	Intersect N. & S. line, 37 lks. S. of post Cor., from which