

Subdivisional Lines, T 5 N R 34 E W M.

Chains

I run

S.89°44' W. on true line.

39.82 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mounds, as per instructions.

79.74 To post Cor.

Land; broken.

Good grass.

Soil; 2nd rate.

N. bet. Secs. 9 & 10.

Var. 20°E.

40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.

80.00 Set post Cor. for Secs. 3, 4, 9 & 10. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Soil; 2nd rate.

Grass good.

April 14th, 1865.

E. on random bet. Secs. 3 & 10.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.86 Intersect N. & S. line, 58 lks. S. of post Cor., from which,

I run

S.89°35' W. on true line.

39.93 Set $\frac{1}{4}$ Sec. post Cor.

Drove charred stake; dug pits & raised mound, as per instructions.

79.86 To post Cor.

Land; broken.

Grass good.

Soil; 2nd rate.

N. on random bet. Secs. 3 & 4.

Var. 21°E.